

90228 ✓

7-161W Map No. K-83

OPER CITIES SERVICE OIL CO. - Liberal,
Ks.

WELL #1 STALCUP "D"
R Holm Drlg.

FIELD Gooch Field Ext (Mrw & Miss)

I.P. Ga 5,000,000 Cfgpd & 5 B Cond/MM, Mrw 6305-
27 (OA)

DST #1 (Mrw) 6241-71, Op 1 hr, R 10' M, No ISIP, FP's
17-17#, FSIP 17#/30"

DST #2 (Mrw) 6280-6330, Op 1 hr, GTS/26", Ga 431,000
Cfgpd/30", Ga 500,000 Cfgpd/60", R 230' GCM, No ISIP,
FP's 124-176#, FSIP 1800#/30", RTD 6651, Log, 5½"
@6650 w/350 sx.

CO 6609, GRN Log, Pf 40/6561-71 (Chest), no sho
nat, 500A (15%), § 1d- 3000A, § 1d w/sll sho oil, Frac
15,000 GA (3%) x 15,000# sd, § 16 1/2 BNO (Gr 42.8 deg)
& 23 1/2 BW/10 hrs & sho gas -§ 2 BO f 9 BW/6 hrs, PB
6368, 28/6320-27, 32/6305-13 (Mrw), Ga 240,000 CFGPD,
nat, 1000A (15%) Ga 1,500,000 CFGPD/4 hrs, SICP 1300#/18
hrs, Frac (22,600 GO (Diesel) x 15,000# sd f 350# hulls)
Rec part 1d, Ga 6,400,000 CFGPD/8 hrs, Ga 4,700,000
CFGPD/19 hrs, Plus heavy mist 1d, 2-3/8" tbg 6319, Ga
1,600,000 CFGPD, Plus 1d oil thru 1½" ck,



S-T-R 31-34S-35W
SPOT C SE SE
CO STEVENS (Ks)
ELEV 3016 KB

- (KB Log)
- Hb 4322 -1306
 - Tor 4344 -3038
 - Lan 4462 -1446
 - Marm 5218 -2202
 - Mo 5926 -2910
 - Mrw sd 6238 -3222
 - Mrw sd 6304 -3288
 - Chest 6330 -3314
 - Chest sd 6558 -3542
 - St G 6598 -3582
 - LTD 6651 -3635

Data Inc

SIP 1385#, 4 Pt COF: 5,000,000 CFGPD f 5 B Cond per
million. SIP 1540#, Mrw 6305-27 (OA) - COMPLETED on
7-12-65

Date of 1st sale of gas 10/25/65

L-53014DF

| | | | |
|-------------|--|---------------------|---------------------------|
| MISCEL DATA | GEOL _____ | ELEV <u>3006 GR</u> | SPUD DATE <u>5-21-65</u> |
| | FTG _____ | <u>3013 DF</u> | DRLG COMP _____ |
| | SUPPT _____ | | FR by DATA <u>5-18-65</u> |
| | CSG <u>8" @1714 w/600 sx. 5" @6650 w/350 sx.</u> | | COMP by " <u>7-15-65</u> |

LIBERAL ELECTRIC LOG TOPS

3016 KB

win 2782 + 234

Heebner 4322 (-1306)

Toronto 4344 (-1328)

Lansing 4462 (-1446)

Marmaton 5218 (-2202)

Morrow 5926 (-2910)

"S-3" Sand 6238 (-3222) 14/34

"S-3" Sand 6304 (-3288) 22/26; ϕ 5,000 MCF

Chester 6330 (-3314)

Sand 6558 (-3542) 14/17 ** 280 + 9 AW / 6*

Ste. Genevieve 6598 (-3582)

TD 6651