


5-105W Map No. K-83 *0-1* *At 9:15 AM* *5/14* *Take over*
 OPER SUNRAY DX OIL CO. & CITIES SERVICE
OIL - WICHITA, KS.
 WELL #1 STALCUP "E"
 UNIT DRG.
 FIELD GOOCH (MRW & MISS)
 I.P. GA 8,000,000 CFGPD, MRW 6276-94



S-T-R 31-34S-35W
 SPOT C SE SW
 CO STEVENS (KS)
 ELEV 3027 KB

Liberal
5-2000 Japs

(KB LOG)	
WIN	2796 + 231
HB	4328 -1301
TOR	4352 -1325
LAN	4468 -1441
MAR	5210 -2183
MRW	5920 -2893
MRW SD	5928 -2901
B/SD	5936 -2909
MRW SD	6250 -3223
B/SD	6264 -3237
MRW SD	6272 -3245
B/SD	6296 -3269
MRW SD	6312 -3285
B/SD	6322 -3295
MRW SD	6340 -3313
B/SD	6354 -3327
CHES	6354 -3327
" SD	6546 -3519
STE.G.	6602 -3575
LTD	6625 -3598

SPUD 3-25-66 8" 1745 W/700 SX. BEN INGOLD - GEOL

NO DST'S, RTD 6625, RNG LOG 4½" 6623 W/200 SX.
 (NOTE: CSO WILL OPERATE FROM PIPE POINT)
 CORRECTED FARM NAME - WAS #1 ERNEST JENNISON, WAS #1 GOOCH
 (CORR ON 3-23-66) - IS #1 STALCUP "E" (CORR 4-21-66)

CO 6573, WELEX BOND & CORR LOG, LD W/500 GAL SW, PF
72/6276-94 (MRW "B"), NO SHO NAT, 500 MA, 8 & FLO LD, GA
 630,000 CFGPD, FRAC 25,000 GSW X 15,750# SD X 40 BALL SEALERS
 8 & FLO PART LD, GA 2,480,000 CFGPD + 25 BWPH - GA 4,280,000
 CFGPD + 25 GWPH, 42 HRS, 1½" TBG SET AT 6301, GA 1,350,000
 CFGPD THRU 1½" TBG, FCP 750#
CAL OF GA 8,000,000 CFGPD, SICP 1501#, MRW 6276-94 -
COMPLETED (5-9-66)

Con't

Data Inc

Connected Aug 17, 1966 PEPL

*(75% working Int.)
 \$ 4/25/66*

(KB SPL)

CHES SH	6340
" SD	6568
STE G	6610
RTD	6625

MISCEL DATA
 GEOL BEN INGOLD ELEV 3024 DF SPUD DATE 3-25-66
 FTG 3015 GR DRG COMP _____
 SUPPT _____ FR by DATA 3-16-66
 CSG 8" 1745 W/700 SX. 4½" 6623 W/200 SX. COMP by " 5-12-66

L-5