


6- 34- 36W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - REPUBLIC NATURAL GAS COMPANY
Farm - Allbritten Trustee No. 1

SEC. 6 T. 34 R. 36W
CS/2 N/2 SE
300' N of Cen. of SE/4

County. Stevens
KANSAS



Total Depth. 2780' SIM

Comm. 1-18-45

Comp. 4-28-45

Shot or Treated. Acid.

Contractor. Moran

Issued. 2-8-47

CASING:

10 1/2" 668' 4" Cem w/150 sx
7 " 2665' Cem w/900 sx

Elevation. 3077m

Production. 28,891,000 Gas

Figures Indicate Bottom of Formations.

red bed	0-577
red bed	710
red bed & shale	750
shale & sand	877
red bed	1050
shale & gyp	1855
anhydrite & lime	1890
blue shale & shells	1938
shale & gyp	2647
brkn lime	2658
lime	2675
lime	2728
red & blue shale	2732
lime	2780
Total Depth S.I.M.	

Original Open Flow: 11,496

Gas Log:

Show of gas	2680-2685	100 MCF (est.)
Increase gas	2740-44	1,311 MCF
Increase gas	2765-70	2,924 MCF
Increase gas	2774-78	12,202 MCF

12 hour close in-Natural flow 12,202 MCF
Well treated April 28th to 30th, 1945 with
8,000 gallons total 15% acid. 72 hour close in
gauged 28,891 MCF