

11-34-36W

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - REPUBLIC NATURAL GAS CO.
Farm - Wheeler No. 1.

SEC. 11 T. 34 R. 36 W
NEc SW
300'S 300'W Cen.



Total Depth. 2799'
Comm. 3-31-46 Comp. 4-21-46
Shot or Treated.
Contractor. Moran Bros.
Issued. 8-3-46

County. Stevens
KANSAS



CASING:
10 3/4" 730'9" Cem.
7" 2650' Cem.

Elevation. 3043

Production. 16,668,000 G.

Figures Indicate Bottom of Formations.

surface sand & clay	0-212
sand & clay	730
red bed	900
shale & sand	960
shale & gypsum	1195
sand	1350
shale & gypsum	1726
lime & anhydrite	1757
shale & gypsum	2308
anhydrite & lime	2650
Herrington lime	2660
lime	2750
shale blue	2757
red rock	2765
lime	2796
shale blue	2799
Total Depth.	

Ran 6 jts. or 175'5" of
5 1/2" liner

Well gauged 1,310 MCF before
and after running liner

Gas log: show	2692
sm inc.	2718-39
1,136 MCF	2745
1,310 MCF	2777
1,465 MCF	2785-94
1,310 MCF	2799

Well treated 4-19 & 20, to
4-21-46 w/12,500 Gals. 15%
acid. 20 min. open flow
test after acid, 16,668 MCF