

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas


15-36-36W

Company REPUBLIC NAT. GAS CO.  
Farm E. Davis No. 1.

SEC. 15 T. 34 R. 36 W  
SEc NW

Total Depth. 2860 SIM  
Comm. 2-26-46 Comp. 4-29-46  
Shot or Treated.  
Contractor. Moran Bros.  
issued. 7-20-46

County. Stevens  
KANSAS



CASING:  
10 3/4"  
7"  
5 1/2" liner

695' Cem.  
2669' Cem.  
194' 7"

Elevation. 3070

Production. Open Flow 18,631 MCF  
S.I.P. 411.6 1/2

Figures Indicate Bottom of Formations.

surface	0-50
sand	93
sand & gravel	640
red rock	665
red bed	720
red bed	945
sand	1012
shale & gypsum	1153
red bed & shale	1207
red bed & sand	1414
shale & gypsum	2375
anhydrite & lime	2468
lime	2493
lime	2570
anhydrite & lime	2655
lime	2760
shale blue	2765
shale red	2770
lime	2814
shale red	2835
lime	2860
Total Depth	SIM

Ran 6 jts or 194' 7" of 5 1/2"  
OD 14# liner on drlg line.  
No trouble. Well gauged  
2,173 MCF before and after  
running liner.

Gas Log:

2690	show
2730-60	1,036 MCF
2785-2805	2,070 MCF
2840-62	2,271 MCF

Well was treated by Dowell with  
12,500 gals. 15% acid, April  
25 to April 29, 1946. Open flow  
after acid 18,631 MCF