


Company - REPUBLIC NATURAL GAS CO.
Farm - Foster No. 2

SEC. 18 T. 34 R. 36 W
NEc SW 18-34-36W
225' S & 225' W of Center

Total Depth. 2890
Comm. 3-10-47 Comp. 3-30-47
Shot or Treated.
Contractor. Gabbert & Lindas
Issued. 7-5-47

County. Stevens
KANSAS



CASING:
10 3/4" 776' Cem. w/250 sx.
7" OD 2674' Cem. w/800 sx.

Elevation. 3122 feet

Production. Open flow 29,415,000
Gas.

Figures Indicate Bottom of Formations.

sand	0-100
sand & shale	670
red bed	785
red bed, shale & sand	1165
shale & red bed	1545
shale & shells	1885
shale & lime	2435
shale, gyp & shells	2490
lime & shale	2675
Herington Sdy	2685
lime & shale	2695
lime	2729
lime hrd	2734
lime	2784
shale red & lime	2789
lime	2836
shale red	2840
lime	2844
shale red	2854
lime	2859
lime brkn	2865
lime	2890
Total Depth.	

Gas Log

First Gas	2711	show
Inc. gas	2719	Inc.
Inc. gas	2734-48'	792 MCF
Inc. Gas	2748-67'	915 MCF
Inc. gas	2767-70'	1,121 MCF
Inc. gas	2775-78'	1,210 MCF
Inc. gas	2778-98'	1,210 MCF
Inc. gas	2854-65'	2,197 MCF
Inc. gas	2865-70'	2,426 MCF
Inc. gas	2870-80'	2,426 MCF
Inc. gas	2880-90'	2,623 MCF

Tops:

Hollenberg	2621
Sandy Herington	2671
Herington Xlyn	2679
Rose Herington	2695
Krider	2724
Odell	2784
Winfield	2789
Gage	2826
Fort Riley	2850

Well was treated 4-9, 11, 14, & 18, 1947
w/14,200 gals. of 15% acid & 12,000 gals.
of 7 1/2% acid. Well gauged 29,415 MCF
after acid on 20 min. open flow, 72
hr. shut in.