

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY

412 Union National Bldg. Wichita, Kansas


24-34-36W

Company - STANOLIND OIL AND GAS COMPANY
 Farm Lucretia Bivans No. 1

SEC. 24 T. 34 R. 36W
 CSE¹/₄

Total Depth. 2800'
 Comm 1-1-48 Comp. 1-27-48 ✓
 Shot or Treated.
 Contractor.
 issued. 4-10-48

County. Stevens
 KANSAS



CASING:
 10-3/4" 725' Cem. w/350 sx
 7" 2660' Cem. w/350 sx

Elevation. 3037 *ind*

Production. 20 Min. Open Flow
 11,766,000 Gas

Figures indicate Bottom of Formations.

| | |
|-----------------------|-------|
| clay, sand & shale | 0-200 |
| sand, shale & red bed | 725 |
| red bed | 925 |
| red bed & anhydrite | 1860 |
| red rock & anhydrite | 2150 |
| lime & red rock | 2265 |
| red rock & gypsum | 2335 |
| lime & shale | 2430 |
| lime & gypsum | 2500 |
| gypsum & anhydrite | 2555 |
| lime & gypsum | 2720 |
| lime & shale blue | 2760 |
| shale & lime | 2785 |
| shale | 2800 |
| Total Depth | |

Schlumberger ran to 2796

Acidization:

Dowell acidized all zones w/1500 gal.
 15%. Displaced Max. press. 575#. Broke
 to 160#, time 37 min. All zones REAW
 13,500 gal. 15%. 10,200 gal. flush,
 using 6 pump trucks, Max. Press. 300#.
 Broke to 50#. Time on Acid 13 min., on
 water 15 min.

Tops:

| | |
|------------|-----------|
| Hollenberg | 2660-2674 |
| Herington | 2682-2696 |
| Krider | 2710-2754 |
| Winfield | 2770-2800 |