

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

J.M.HUBER CORP.
Dunne-Hoffman No. 3


SEC. 9 T. 34 R. 37 W.
Center SE $\frac{1}{4}$

Total Depth. 2898
Comm. 3-15-42 Comp. 4-29-42
Shot or Treated.
Contractor.
Issued. 6-27-42

County Stevens.

CASING.

Rotary 2658
Cable 2898



103/4" 611' cemented.
7" 2650' cemented.
5 1/2" liner 285 set at 2898.

Elevation.

Production. 7,000,000 Gas.

Figures Indicate Bottom of Formations.

surface sand	40
sand and caliche	261
caliche, sand & yellow clay	570
red bed	980
gyp	1045
red bed and sand	1282
red rock & gyp and shells	1527
sdv shale and red rock	1720
anhydrite	1780
dolomite	1820
sand and shale	2290
dolomite and anhydrite	2640
sand and dolomite	2658
anhydrite and red shale	2670
sand and dolomite	2675
dolomite	2705
red shale	2710
dolomite	2735
shale red	2740
dolomite	2750
red sand	2760
dolomite	2795
sand and red shale	2815
limestone	2863
sand	2875
sdv lime	2898

Total Depth.

Sand Record.

1st show gas	2660
Inc.	2685
Inc.	2710
Inc.	2745-50
Inc.	2777-95 2 MM
Inc.	2820-60

7 Million