

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


12-34-37W

Company - REPUBLIC NATURAL GAS CO.
Farm - Springer No. 2

SEC. 12 T. 34 R. 37 W
SWc NE
250' N & 100' E of Center

Total Depth. 2851' SIM
Comm. 1-6-46 Comp. 2-17-46
Shot or Treated.
Contractor. Coppinger & Southern
issued. 4-6-46

County. Stevens
KANSAS



CASING:
10 3/4" 629'13" Cem.
7" 2647'35" Cem.

Elevation. _____

Production. 21,670,000 Gas
R. P. 394.5#

Figures Indicate Bottom of Formations.

sand	0-319
sand, red rocks	645
red rock, gravel	725
sand, red bed	1128
sand, shells	1725
shale, lime	2130
shale	2265
shale, anhydrite	
lime	2365
lime	2405
shale, lime	2483
lime	2540
lime, shale	2600
lime	2657
shale	2670
lime	2715
shale, gy	2720
lime	2725
shale sdy	2740
shale gy	2755
red rock	2765
lime sdy	2775
lime	2795
shale gy	2800
shale red	2805
red rock	2820
shale gy	2826
lime	2851

Total Depth SIM

Ran 7 joints of 5 1/2" Liner.

First gas	2685'	98 MCF
Inc. gas	2710-15'	656 MCF
Inc. gas	2725-30'	1136 MCF
Inc. gas	2735-40'	1597 MCF
Inc. gas	2775-95'	2458 MCF
Inc. gas	2826-50'	2661 MCF

72 hr. close in - Nat. flow 2,661 MCF.
Well treated 2-22-46 to 2-24-46,
w/12,500 gals. 15% acid. 72 hr. shut
in caused 21,670,000. R. P. 394.5#