

16-34-37W


KANSAS DRILLERS LOG

S. 16 T. 34S R. 37 E
W

Loc. 1250' FN&WL

County STEVENS

640 Acres
N



Locate well correctly
3176.2'

Elev.: Gr.

DF KB

API No. 15 — 189 — 20,411
County Number

Operator

ANADARKO PRODUCTION COMPANY

Address

P. O. BOX 351, LIBERAL, KANSAS 67901

Well No.

1

Lease Name

DUNNE-HOFFMANN "G"

Footage Location

1250 feet from (N) XX line 1250 feet from (E) (W) line

Principal Contractor

Gabbert-Jones, Inc.

Geologist

Spud Date

5/15/78

Total Depth

3120'

P.B.T.D.

3100'

Date Completed

6/2/78

Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	727'	Common	600	3% cc
Production	7-7/8"	4-1/2"	10.5#	3120'	Lite Wate SS Poz	500 150	4% gel .5% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		3033-3097'

TUBING RECORD

Size	Setting depth	Packer set at
2-1/16"	3060'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/3300 gals 15% + 130 BS; F/100,000 gals wtr, 150,000# riversand	3033-97'

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
SI FOR PL		Flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	2530 MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
WILL BE SOLD			3033-97' Council Grove		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

