

90082

K-83

12-144W		MAP NO.		SEC 13-34S-37W	
STATE	Kans	COUNTY	Stevens	LOC.	C SW NE
OPER	Mobil Oil Co. - Wichita, Kansas				FT/FR
WELL	2	FARM	Cunningham Unit #126	FT/FR	LIN
POOL	Voorhees	ELEV.	3125 EGR	DF	3136
CONT.	Graham Michaelis	GEOL.	Tom Robinson & W.H. Sorensen		
CO.	6850' Oil Test				
INT.	10-16-64	SPUD	10-17-64	COMP.	12-15-64
F.R.	6914	FM.	St Gen	PBTD.	6450
TD	PRODUCING FM.		FROM	TO	PERF W/HOLES
Completion Record	L/Morr		6313-6351	24	568A & Frac
	COF: 334,900 Cfgpd, WP 410#				
Casing Record	8" @1773 w/475 sx.		4½" @6913 w/300 sx.		

Data Inc.

(KB Log)

Chase 2724 + 409
 Winf 2785 + 348
 CG 3026 + 107
 Adm 3280 - 147
 Wab 3434 - 307

(Cont Below)

Ø #1 (St L) 6745-6802, R 56' (13' lm, gry tan, dns fn xln, foss - hard, vert fracs, tite, NSO & 31' lm, tan, fn-med ool, foss no vis por, NSO & 4' lm, drk gry dns & 5' lm, gry - tan ool, hi fracs, G/F vis inte ool por & sli oil stn & 3' lm, gry dns fo sli ool, fract'd, NSO, RTD 6914, Sj Log,

Shaw 3808 - 675
 Hb 4274 -1141
 Lans 4326 -1213
 Marm 5148 -2015
 Chero 5248 -2295
 Morr 5950 -2817
 L/Morr sd 6310 -3174
 B/Morr sd 6318 -3182
 L/Morr sd 6345 -3209
 B/L Morr sd 6354 -3218
 Chest 6374 -3241
 St G 6572 -3439
 St L 6740 -3607
 LTD 6912 -3776
 (DF Spl)
 Hb 4275
 Lans 4345
 Marm 5155
 Chero 5435
 Morr 5950
 L/Morr 6307
 M Chest 6378

4½" @6913 w/300 sx., CO 6865, Pf 24/6840-46 (St L), \$ no flu - nat, 250A (15%), \$ 1d & 23 BSW/10 hrs (Clor 81,300 PPM), PB 6825, Pf 16/6750-54 (St L), \$ no flu - na 250A (15%), \$ 1d, no sho, PB 6450, Pf 12/6347-51 & 12/6313-17 (L/Morr), no sho - nat, 568A (7½%), \$ 1d w/scum oil & sli sh gas, Frac 20,000# sd x 20,000 GA, Flo 1d, Ga 700,000 Cfgpd/5 hrs, 2 3/8" tbg @6275, Flo 537,000 Cfgpd/5 hrs thru 2" tbg & 8 BWP/last 2 hrs, Flo test 24 BSW/24 hrs & 280,000 Cfgpd thru 20/64" choke, TP 100#, Sep Pr 23#, SI/24 hrs, SITP 1380#, Blew 45" - NW, 28 hr SIP 1450#, Blew 45" - Flu to surf in 30", PBTD 6450, 72 hr BHP 1827 98 hr BHP 1845#, SIP 1603#, COF 334,900 Cfgpd, WP 410#, L/Morr pfs 6313-6351 - COMPLETED (12-7-64)
 Corrected on 12-9-64 from #1 Cunningham Estate to #2 Cunningham Unit #126

St G 6560
 RTD 6914 -3778

608648

LIBERAL ELECTRIC LOG TOPS

3136 KB

Winfield 2784 (/352)
Council Grove 3040 (/96)
Heebner 4286 (-1150)
Toronto 4300 (-1164)
Lansing 4416 (-1280)
Marmaton 5146 (-2010)
Morrow 5950 (-2814)
"S-3" 6308 (-3172) 6/10; Ø 334 MCF
Chester 6354 (-3218)
Ste. Gen 6594 (-3458)
St. Louis 6714 (-3578)
TD