

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG WICHITA KANSAS

Plotted ✓

15-34-38W

Location Cen NE/4

STANDARDIZED AT 2565'

Sec. 15 T. 34 R. 38W.

Casing Record

County- Stevens.

Nov 24 1930

10" 625' Farm- Kelly No. 1
 20" 8 1/4" Company- Texas-Interstate Pipe Line.
 15 1/2" 65/8" 2565 Contr.- Charles A. Conley.
 12 1/2" 53/16" Comm.- 8/20/30 Comp.- 11/3/30.
 Total Depth 2832' SLM Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to



Elevation 323'

Figures Indicate Bottom of Formations.

Initial Production

Date Issued. 11/22/1930.

9,717,000 cu. ft. Gas.

Formation	Depth	Formation	Depth	Formation	Depth
surface	140	lime	2312	lime	2720
sand	264	brkn lime & red beds	2320	shale	2730
sand	555	lime	2335	sandy	2735
gravel	605	sticky shale	2339	lime Gas	2740
red bed	625	lime	2354	lime & gas	2765
sand	647	gyp sand & sticky		red rock	2770
GYP	667	shells	2370	red rock	2785
red rock	688	stick shale hrd	2380	Gas tested 2.3 Hg	
brkn gyp	1040	gyp	2382	through 6 5/8" opening	
red bed sand & gyp	1057	lime	2390	at 2775'	
red bed	1150	shale	2393	red rock	2790
brkn lime	1177	shale	2396	Gas 2790-2827'	
red bed	1192	anhydrite	2403	lime	2832
brkn gyp	1225	sanhydrite	2409		
water sand	1250	shale	2412	Total Depth SLM	2832'
sticky red beds	1275	anhydrite	2417		
red beds	1280	anhydrite	2420		
sand	1283	shale	2427		
water sand	1315	lime	2431		
sand & lime	1336	GYP	2432		
sand	1345	GYP	2438		
sand	1347	GYP	2443		
sand	1540	lime	2447		
red beds	1600	GYP	2450		
red beds	1706	anhydrite	2462		
brkn lime	1724	shale	2465		
water sand	1754	lime	2467		
red bed S.G. 1799'	1785	lime	2472		
gyp & red beds	1804	shale	2475		
lime	1821	GYP	2480		
brkn lime	1825	anhydrite	2484		
sdv lime	1827	shale	2486		
lime	1828	anhydrite	2489		
red beds & gyp shells	1904	anhydrite brkn with			
gyp shells	1916	shale	2501		
red beds	2020	slate	2505		
sand	2032	anhydrite	2516		
sand	2037	shale	2520		
red beds	2067	shale & shells	2526		
shale	2170	shale & anhydrite			
lime	2186	brkn	2539		
shale & shells	2189	anhydrite	2558		
sdv lime	2193	anhydrite	2562		
sdv lime	2199	lime	2565		
sticky shale	2218	Standardized & set			
lime	2221	6 5/8" csg. at 2565'			
sand	2224	lime	2578		
sticky shale	2229	lime & shale	2596		
sandy lime	2237	shale	2602		
red beds hrd	2253	lime	2610		
lime	2260	shale	2615		
shale	2271	lime	2632		
red beds	2295	shale	2645		
GYP	2297	lime	2675		
GYP	2299	1st gas at 2650'			
lime	2306	Gas 2665-75'			
		sdv lime	2700		