

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock,


Wichita, Kansas 15-34-38W

Company- ANADARKO PRODUCTION CO.  
Farm- Kelley "B" No. 1A

SEC. 15 T. 34 R. 38W  
C SW

Total Depth. 6590' PB 3100'  
Comm. 9-23-60 Comp. 11-29-60  
Shot or Treated.  
Contractor. Schafer Drlg.  
Issued. 8-12-61

County Stevens  
KANSAS



Elevation. 3232' GL

Production. 409,000 CFG

CASING:

13 3/8" 599' cem w/500 sx.  
4 1/2" 3135' cem w/150 sx.  
1 1/4" 3077'

Figures indicate Bottom of Formations.

sand & red bed 600  
sand & shells 724  
red bed & gypsum 1081  
red bed & shells 1245  
sand & gypsum 1350  
gypsum 1368  
sand 1472  
sand & anhydrite 1511  
sand & red bed 1523  
red bed, anhydrite & sand 1708  
sand & anhydrite 1781  
anhydrite & shale 2425  
shale & shells 2585  
anhydrite & shale 2800  
lime & shale 3930  
lime 4112  
lime & shale 5250  
lime & chert 5319  
lime, chert & shale 5492  
lime & shale 6590  
Total Depth  
Plugged back to 3100'

TOPS: SCOUT

Krider 2645  
Winfield 2734  
Council Grove 2965  
Admire 3214  
Wabaunsee 3396  
Toronto 4245  
Lansing 4351  
Marmaton 5072  
Cherokee 5348  
Morrow 5890  
Lower Morrow Sand 6329  
Mississippi Chester 6379  
St. Genevieve 6542

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION

Name	From	To	No. of Shots	Gallons Used	Kind Used
Council Grove	3044	48	8	1,000	15%
Council Grove	3052	56	8	10,000	7 1/2%