



1-34-38W

DRILLER'S LOG

API#15-189-20,183

WELL NAME Kimzey "A" #1

COMPANY OPERATING Anadarko Production Company
ADDRESS OF COMPANY Box 351, Liberal, Kansas 67901WELL LOCATION C $\frac{1}{4}$ NE $\frac{1}{4}$ $\frac{1}{4}$ 1320 Ft. ~~XXXXXX~~ South Line, South of North Line1320 Ft. ~~XXXXXX~~ Sec. 1, Twp. 34S, Rge. 38W, Stevens County, Kansas
West of East Line

DRILLING STARTED April 2, 19 73, DRILLING COMPLETED April 15, 1973

WELL COMPLETED May 7, 19 73, WELL CONNECTED, 19

ELEVATION 3167 Ft. Ground Level CHARACTER of WELL (Oil, Gas, Dry Hole) Gas

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION

Name	From	To	No. of Shots	Gallons Used	Kind Used
Council Grove	3072	3075	6	Acid w/500 gallons	15% regular
"				Squeezed w/100 sx common.	
"	3047	3050	6	Acid w/500 gallons	15% regular
"				Set CIBP @ 3038'	
"	3023	3028	10	Acid w/500 gallons	15% regular
"				Squeezed w/100 sx common.	
"	2999	3003	8	Acid w/500 gallons	15% regular
"				Squeezed w/100 sx common.	
"	2979	2981	6	Acid perfs 2972-81'	OA w/750 gals
	2972	2975	9	15% regular.	

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8-5/8"	1739'	1000	
5-1/2"	3156'	650	
2-1/16" tubing, set @ 2921'		SN @ 2905'	

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surf soil, sand & clay	0	560	Total Depth	3156	
Red bed	560	820			
Red bed, sand & anhy	820	1225			
Red bed, sd, stks.					
anhy	1225	1495			
Red bed & anhy	1495	1739			
A - shale	1739	1882			
Red bed, shale &					
shells	1882	2194			
Shale & shells	2194	2337			
Shells - shale	2337	2520			
Lime	2520	2895			
Core	2895	3156			

RESULTS OF INITIAL PRODUCTION TEST: CWHOF 4011 MCFD (check test) taken 5-17-73

Council Grove	2958	2961	9	Acid perfs 2924-61' OA w/2000 gals
"	2945	2951	24	15% regular. Fraced perfs 2924-81'
"	2935	2937	6	w/80,000 gals wtr & 60,000# riversand
"	2930	2932	6	
"	2924	2926	6	