

DRILLER'S LOG

2-34-38W

WELL NAME Bane "E" #1 COMPANY OPERATING Anadarko Prod. Co.
 ADDRESS OF COMPANY Box 351, Liberal, Ks. 67901
 WELL LOCATION $\frac{1}{4}$ $\frac{1}{4}$ $\frac{1}{4}$
1250 Ft. North of South Line,
1370 Ft. ~~XXXXXXXXXXXX~~, Sec. 2, Twp. 34S, Rge. 38W, Stevens County, Kansas
 From East Line
 DRILLING STARTED 5-3, 19 74, DRILLING COMPLETED 5-7, 19 74
 WELL COMPLETED 5-27, 19 74, WELL CONNECTED _____, 19 _____
 ELEVATION 3169 Ft. Ground Level CHARACTER of WELL (Oil, Gas, Dry Hole) Gas

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Council Grove	2983	2996	26	Acidized w/500 gals 15% 100 sx common.	Sq w/
"	2913	2916	9	Acidized 2913-78'	OA w/2000 gals
"	2919	2924	15	15% HCL + 120 BS.	Fraced w/80,000
"	2927	2933	18	gals wtr + 60,000#	riversand.
"	2936	2947	33		
"	2952	2957	15		
"	2963	2967	12		
"	2970	2978	24		

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8-5/8"	646'	450	None
5-1/2"	3020'	650	None
2-3/8" tubing, set @ 2953'		SN @ 2936'	None

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Clay & sand	0	605			
Red bed	605	670			
Red bed & sand	670	1370			
Shale & anhydrite	1370	1747			
Shale & lime	1747	3020			
Total Depth	3020				

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 25 1974
 CONSERVATION DIVISION
 Wichita, Kansas

RESULTS OF INITIAL PRODUCTION TEST: IWHOF 3093 MCFD (one-point check test)