

Plotted
2-34-38W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG, WICHITA KANSAS

Location Center NE $\frac{1}{4}$

Sec. 2 T. 34 R. 38W


Casing Record.

20" 133/8 658'1
8 1/4"
15 1/2" 65/8" 2620'8
53/16"

Farm. Shirley
Company. Texas Interstate Pipeline Co.
Contr.
Comm. 2-17-31

County. Stevens. APR 25 1931

No. 1



Total Depth. 2805 Shot Quarts Betwee n.

Correspondence Regarding This Well Should Be Referred To.

Elevation. 3169

Figures Indicate Bottom of Formations.

Initial Production.

Date Issued. 4-25-31.

6,256,000 Gas. R.P. 420#

ROTARY TOOLS.

Formation	Depth.
sand	255
sand and gravel	628
lime and shells	632
red bed and shells	641
red bed and gyp	1041
broken lime	1061
sand hard	1101
sand red bed and gyp shells	1436
red bed and gyp shells	1666
lime	1700
broken lime	1829
red bed and lime	1885
broken lime	1925
lime hard	1951
red bed and gyp	1971
broken lime	2030
red bed and lime	2072
broken lime	2200
lime and blue shale	2240
lime	2295
Anhydrite	2500
Anhydrite and blue shale	2539
lime	2549
anhydrite	2565
lime hard	2570
anhydrite and brown shale	2578
shale blue and shells	2595
lime	2599 Finished March 11, 1931.

CABLE TOOLS.

lime	2665 Began rigging up 3/20/31
red bed	2680
lime	2720
red rock	2750
lime	2780
shale blue	2805

T.D. Show of gas 2605. More gas at 2770
More gas at 2690 Steel line Run 2805.
More gas at 2710