


9-34-38 W

S. 9 T. 34S R. 38 ^{EX} W
 Loc. 1250' FS&WL
 County Stevens



Elev.: Gr. _____
 DF _____ KB 3256.13'

KANSAS DRILLERS LOG

API No. 15 — 189 — 20,264
 County Number

Operator
Anadarko Production Company

Address
Box 351, Liberal, Kansas 67901

Well No. #1 Lease Name Taylor "C"

Footage Location
 1250' feet from (NS) (S) line 1250 feet from (E) (W) line

Principal Contractor Geologist
Gabbert-Jones, Inc.

Spud Date Total Depth P.B.T.D.
 2-21-75 3065'

Date Completed Oil Purchaser
 3-15-75

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	618'	Common	500	3% CC
Production	7-7/8"	4-1/2"	10.5#	3064'	Lite Wate Pozmix	575 150	4% gel 12 1/2# Gilson 18% salt .5% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3 SPF		2968' - 3024' OA

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8"	2958'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/2000 gallons 15% + 125 ball sealers. Fraced w/80,000 gallons water + 60,000# Riversand.	2968' - 3024' OA

INITIAL PRODUCTION

Date of first production SI for pipeline connection Producing method (flowing, pumping, gas lift, etc.) Flowing

RATE OF PRODUCTION PER 24 HOURS Oil Gas Water Gas-oil ratio
 bbls. WHOE 2611 MCF bbls. CFPB

Disposition of gas (vented, used on lease or sold) Will be sold Producing interval (s) 2968' - 3024' OA Council Grove A

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **Anadarko Production Company** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. #1 Lease Name Taylor "C" Gas

S 9 T 34S R 38 ^{XE} W


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Clay-Sand	0	578		
Redbed	578	1125		
Redbed-Anhy-Sand	1125	1506		
Shale-Anhy	1506	1925		
Shale-Lime	1925	2391		
Lime-Shale	2391	3065		
Total Depth		3065		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



T. W. Williams
Signature

T. W. Williams
Division Office Supervisor
Title

March 25, 1975
Date

2006th