


10-34-38W

KANSAS DRILLERS LOG *State Geological Survey*
WICHITA, BRANCH
 20,288
 API No. 15 — 189 —
 County Number

S. 10 T. 34S R. 38 E
 W
 Loc. 1390' FWL & 100' FSL
 County Stevens



640 Acres
 N
 Locate well correctly
 Elev.: Gr. 3234.3'
 DF _____ KB _____

Operator
 Anadarko Production Company

Address
 P. O. Box 351, Liberal, Kansas 67901

Well No. 1 Lease Name Coulter "A"

Footage Location
 100 feet from (N) (S) line 1390 feet from (E) (W) line

Principal Contractor Gabbert-Jones, Inc. Geologist _____

Spud Date 10-19-75 Total Depth 3040 P.B.T.D. _____

Date Completed 11-6-75 Oil Purchaser _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	565'	Common	550	3% CC
Production	7-7/8"	4-1/2"	10.5#	3035'	Lite Wate Pozmix	500 150	4% gel 12 1/2# Gilsni .5% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3 SPF		2946-3004' OA

TUBING RECORD

Size	Setting depth	Packer set at
2-1/16"	3006'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/2000 gallons 15% + 105 ball sealers. Fraced w/80,000 gallons water + 80,000# Riversand.	2946-3004' OA

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.)
 SI for Pipeline Connection Flowing

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	CWHOF 3120	MCF	bbls. CFPB

Disposition of gas (vented, used on lease or sold) Will be sold Producing interval (s) Council Grove A 2946-3004' OA

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Anadarko Production Company

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

1

Lease Name

Coulter "A"

Gas

S 10 T 34S R 38 E W


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Clay-Sand	0	200		
Sand-Clay	200	540		
Redbed	540	1035		
Redbed-Anhydrite-Sand	1035	1480		
Sand-Shale	1480	1761		
Redbed-Anhydrite	1761	2189		
Shale	2189	2251		
Shale-Lime	2251	2324		
Lime-Shale	2324	3040		
Total Depth		3040		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



49908

Stanley Shoemaker
 Stanley Shoemaker Signature
 Division Office Supervisor Title

November 7, 1975

Date

2-2d-280