

12-34-38W

KANSAS DRILLERS LOG


State Geological Survey
WICHITA, BRANCH

S. 12 T. 34S R. 38W E
Loc. 1250' FN&WL

API No. 15 — 189 — 20,236
County Number

County Stevens

640 Acres
N



Locate well correctly
Elev.: Gr. 3174'

DF _____ KB _____

Operator
Anadarko Production Company

Address
Box 351, Liberal, Kansas 67901

Well No. 1 Lease Name Greenwood "A"

Footage Location
1250 feet from (N) line 1250 feet from (E) (W) line

Principal Contractor Gabbert-Jones, Inc. Geologist _____

Spud Date 2-27-74 Total Depth 3010' P.B.T.D. _____

Date Completed 3-25-74 Oil Purchaser _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	18#	633'	Common	575	3% CC
Production	7-7/8"	5-1/2"	14# & 17#	3010'	LiteWate	500	4% gel + 12-1/2# Gilsonite/sack
					Pozmix	150	18% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		2925-86' OA

Size	Setting depth	Packer set at
2" & 2-1/16"	2934'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/2000 gallons 15% HCL + 115 BS. Fraced w/ 80,000 gallons water + 60,000# riversand.	2925-86' OA

INITIAL PRODUCTION

Date of first production Not connected as yet Producing method (flowing, pumping, gas lift, etc.) Flowing

RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas COF 4744 MCF	Water bbls.	Gas-oil ratio	CFPB
---------------------------------	-----------	------------------	-------------	---------------	------

Disposition of gas (vented, used on lease or sold) Will be sold Producing interval (s) 2925-86' OA

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Anadarko Production Company

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

1

Lease Name

Greenwood "A"

Gas Well

S 12 T 34 S R 38 W E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Clay & sand	0	610	Top:	
Red bed	610	790		
Red bed & shells	790	1425	Council Grove	2921'
Shale & anhydrite	1425	1817		
Lime & shale	1817	2092	Log:	
Shale & shells	2092	2332		
Lime & shale	2332	2981	Nuclear Log	1500-2991'
Lime	2981	3010		
Total Depth	3010			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



T. W. Williams
 T. W. Williams Signature
 Division Office Supervisor
Title
 April 17, 1974
Date

610677