

STEVENS COUNTY OIL & GAS CO.  
Finch No. 1.

SEC. 13 T. 34 R. 38W  
Cen SW  $\frac{1}{4}$


13-34-38W  
County. Stevens

Total Depth. 2835'  
Comm. 11-12-36 Comp. 12-6-36  
Shot or Treated.  
Contractor.  
Issued. 12-26-36

CASING.

10  $\frac{3}{4}$ " 676'  
7 " 2550'

DEC 26 1936



Elevation.

Production. 6,635,000 Gas

Figures Indicate Bottom of Formations.

|                        |      |
|------------------------|------|
| water sand & clay      | 418  |
| sand & red bed         | 672  |
| red bed shells         | 1350 |
| shells & shale         | 1520 |
| anhydrite & shells     | 1568 |
| red bed & shells       | 1770 |
| shale & anhydrite      | 1893 |
| shale & shells         | 2075 |
| shale & shells         | 2301 |
| shale & anhydrite      | 2346 |
| shale                  | 2365 |
| anhydrite              | 2385 |
| shale                  | 2444 |
| shale & anhydrite      | 2538 |
| lime                   | 2550 |
| lime hrd               | 2565 |
| shale & shells         | 2585 |
| lime shells            | 2590 |
| shale                  | 2595 |
| lime shell             | 2600 |
| sand lime (gas)        | 2605 |
| sand lime (gas inc.)   | 2610 |
| sdv lime               | 2626 |
| red bed                | 2632 |
| lime hrd               | 2675 |
| lime shells & sdv lime | 2700 |
| shale & red bed        | 2710 |
| red bed                | 2718 |
| lime hrd               | 2748 |
| lime sdv               | 2760 |
| red bed                | 2780 |
| lime hrd               | 2785 |
| grey & blue shale      | 2790 |
| sdv lime gas inc.      | 2795 |
| sdv lime               | 2831 |
| shale grey             | 2835 |
| Total Depth.           |      |