

13-34-38W

KANSAS DRILLERS LOG

API No. 15 — 189 — 20,256
County Number

Operator

Anadarko Production Company

Address

P. O. Box 351, Liberal, Kansas 67901

Well No.

1

Lease Name

STUART "A"

Footage Location

1250

feet from (N) ~~XXX~~ line

1250

feet from ~~XXX~~ (W) line

Principal Contractor

Gabbert-Jones, Inc.

Geologist

Spud Date

1-14-79

Total Depth

3040

P.B.T.D.

3027

Date Completed

2-2-79


Oil Purchaser

S. 13 T. 34S R. 38 ~~xx~~ W

Loc. 1250' FNL & 1250' FWL

County Stevens

640 Acres
N



Locate well correctly
3186.8

Elev.: Gr.

DF

KS

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	710	Common	600	3% CaCl
Production	7-7/8"	4-1/2"	10.5#	3037	SS Poz Lite Wate	150 500	.5% Cfr-2 4% Gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		3020-25' 3004-14'
TUBING RECORD					2990-3000'
Size	Setting depth	Packer set at			2976-86'
2-3/8"	2950'				2962-70'


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/4000 gal 15% Hcl + 110 BS	2962-3025 OA
F/100,000 gal wtr + 150,000# riversand	2962-3025 OA

INITIAL PRODUCTION

Date of first production SI for PL	Producing method (flowing, pumping, gas lift, etc.) Flowing
RATE OF PRODUCTION PER 24 HOURS	Oil 0 bbls. Gas 809 MCF Water 0 bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold) Sold	Producing interval(s) 2962-3025 OA

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Anadarko Production Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 1	Lease Name STUART "A"		Gas
S 13 T 34S R 38 ^{XX} W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
DEPTH			
Surface Clay-Sand-Redbed	0	415	
Sand-Redbed	415	715	
Redbed	715	980	
Sand-Redbed	980	1500	
Redbed	1500	1905	
Redbed-Shale-Shale w/Lime	1905	2288	
Lime-Shale	2288	3040	
TD	3040		
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Paul Campbell Division Production Manager		
	Title February 13, 1979 Date		

5206hh