

OP. = WALTER KUHN DRLLG. CO.
CONTR. = GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

18-34-38w

Osman #2
110' N of C-N/2
Stevens County, Kansas

SEC. 18 - T 34 S - R 38 W

API 15-189-20520

Commenced: 9-17-80

Completed: 9-21-80

OPERATOR: Walter Kuhn Drilling Company

Depth	Formation	Remarks
From	To	
0	506	Surface Clay-Sand-Redbed
506	629	Sand-Redbed
629	1528	Redbed-Sand
1528	2059	Sand-Redbed-Anhy
2059	3150	Lime-Shale

Ran 15 jts of 23# 8 5/8" csg set @ 622' cemented w/ 25- sks L.W. - 1/4# Floseal/per sack 2% CC + 150 sks Common 3% CC PD @ 8:30 PM 9-17-80

Ran 79 jts of 9 1/2# 4 1/2" set @ 3145' cemented w/ 600 sks L.W. 4% Gel + 150 sks 60/40 Posmix 10% salt - .5% CFR-2 PD @ 11:30 AM 9-21-80

3150 TD

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss:

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.


GABBERT-JONES, INC.

James S. Sutton II
JAMES S. SUTTON II

Subscribed and sworn to before me this 25th day of September, 1980.

Lola Lenore Costa
LOLA LENORE COSTA
NOTARY PUBLIC

My Commission expires October 20, 1980.



**GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG**

18-34-38W

**Ocean #2
110' N of C-N/2
Stevens County, Kansas**

Commenced: 9-17-80

Completed: 9-21-80

State Geologist Survey
WICHITA BRANCH

OPERATOR: Walter Kuhn Drilling Company

Depth		Formation	Remarks
From	To		
0	506	Surface Clay-Sand-Redbed	
506	629	Sand-Redbed	Ran 15 jts of 23# 8 5/8" csg set @ 622' cemented w/ 25- sks L.W.-
629	1528	Redbed-Sand	1/4# Floeal/per sack 2X CC +
1528	2059	Sand-Redbed-Anhy	150 sks Common 3X CC PD @ 8:30 PM
2059	3150	Line-Shale	9-17-80
			Ran 79 jts of 9 1/2# 4 1/2" set @ 3145' cemented w/ 600 sks L.W. 4X Gel + 150 sks 60/40 Posmix 10X salt - .5X CFR-2 PD @ 11:30 AM 9-21-80

3150 TD

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss:

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
JAMES S. SUTTON II

Subscribed and sworn to before me this 25th day of September, 1980.

Lola Lenore Costa
LOLA LENORE COSTA
NOTARY PUBLIC

My Commission expires October 20, 1980.

