


22-34-38W 9.2.7
card made outSTEVENS COUNTY OIL & GAS CO.
Burrows No. 1.SEC. 22 T. 34 R. 38W
Cor NW $\frac{1}{4}$ Total Depth. 2895'
Comm. 5-1-38 Comp. 6-10-38
Shot or Treated, 2000 & 7000 Gals.
Contractor.
Issued. 8-13-38

County. Stevens

AUG 13 1938

CASING:
10 3/4"
7"617'
2560'

Elevation.

Production. 8,700,000 G.
R.P. 435 $\frac{1}{2}$

Figures Indicate Bottom of Formations.

surface sand	108	lime & shale	2590
sand & clay	410	shale & anhydrite	2610
gravel hrd	576	lime grey	2625
sand & gravel	612	lime	2640
red bed	617	lime & shells	2650
red bed & shells	1130	lime hrd	2660
shale & shells	1170	lime	2685
sdv shale	1200	lime hrd	2710
GYP	1230	lime grey	2726
red bed & sand	1315	shale chocolate	2735
shale & sand	1345	lime hrd	2750
quick sand	1360	lime	2765
	1345 lost circulation	shale	2775
hrd gravel & shale	1410	shale chocolate	2790
GYP	1468	lime grey	2805
GYP	1515	lime sdv	2814
red bed & shale	1703	lime sdv blue	2820
sticky shale & gyp	1765	lime sdv	2845
hrd anhydrite	1780	shale	2862
anhydrite	1805	lime grey	2875
shale & shells	1890	lime sft	2888
sdv lime	1921	lime hrd	2895
brkn anhydrite	1945	Total Depth.	
shale red & sticky anhyd.	1958		
anhydrite	1985		
shale	2009	Gas Log	
shale & shells	2035	1st sh gas	2630-2640
anhydrite	2076	inc in gas	slight 2735-2750
shale	2130	inc in gas	2762 open flow 2,000,000 G
anhydrite	2178		
shale & shells	2228	2000 Gals.	
anhydrite & shale brks	2295	7000 Gals. Open flow	6,500,000 G.
anhydrite	2350		
shale	2380		
anhydrite hrd	2445		
anhydrite brkn	2450		
shale	2455		
shale	2462		
anhydrite	2533		
shale blue & shells	2561		
sdv lime	2577		