

22-34-38W

State Geological Survey
WICHITA BRANCH

KANSAS DRILLERS LOG

S. 22 T. 34 R. 38 E
Loc. 1250' FSL & 1750' FEL
County Stevens

API No. 15 - 189 - 20409
County Number

Operator
Kaiser - Francis Oil Company

Address
P. O. Box 35528 Tulsa, Oklahoma 74135


Well No. #2 Lease Name Kelley "B"

Footage Location
1250' feet from (N) (S) line 1750' feet from (E) (W) line

Principal Contractor Service Drilling Company Geologist None

Spud Date 4/22/78 Total Depth 3150' P.B.T.D. 3060'

Date Completed 4/22/78 Oil Purchaser



Locate well correctly
Elev.: Gr. 3208'
DF 3212' KB 3215'

5/30/78 CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	555"	Halliburton Light Class H	250 200	2% CaCl 3% CaCl
Production	7-7/8"	5-1/2"	14#	3151'	Halliburton	500 150	HLT 18% salt, 3/4 of 1% CFR-2

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
		None	2		2974-3042' OA

TUBING RECORD		
Size	Setting depth	Packer set at
1.6600	3151'	0

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized down casing with 3000 gals 15% HCL (5/10/78)	} 2974 - 3042
Fraced with 100,000 gals water & 100,000# river sand	

INITIAL PRODUCTION

Date of first production September 6, 1978 Producing method (flowing, pumping, gas lift, etc.) Flowing

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	None	1200 bbls.	2 MCF	-

Disposition of gas (vented, used on lease or sold) Sold Producing interval (s) 2974 - 3042 overall

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

