

26-34-38W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - REPUBLIC NAT. GAS CO.
Farm - A. Burrows No. 1.

SEC. 26 T. 34 R. 38 W
SWc NE
200'E 100'N of Center Sec.

Total Depth. 2845' SLM
Comm. 3-22-46 Comp. 6-21-46
Shot or Treated.
Contractor. Moran Bros.
Issued. 8-3-46

County. Stevens
KANSAS



CASING:
10 3/4" 677' 7" Cem.
7" 2613' 10" Cem.

Elevation. 3186 ft

Production. 33,607,000 G.

Figures Indicate Bottom of Formations.

surface	0-100
sand	165
shale, sand	500
clay	610
sand	685
red bed	850
shale, sand	1075
gypsum	1165
gypsum, red bed	1275
sand	1360
red bed	1490
red bed, gypsum	1625
shale, gypsum	1750
shale, shells	1810
red bed, shells	1820
shale, gypsum	2050
shale, shells	2091
shale, gypsum	2322
anhydrite, shale	2559
anhydrite, lime	2614
lime	2632
shale	2634
lime	2710
shale	2713
lime	2715
red rock	2730
lime	2769
shale red	2785
lime	2845
Total Depth.	SLM

Gas Log:
1st gas 2640 show
inc. 2693 656 MCF
inc. 2700 927 MCF
inc. 2710 1,136 MCF
inc. 2748-69 5,488 MCF
inc. 2815-25 5,399 MCF

No 72-hr open flow test
taken before acid. Well
treated on 6-17-46 to
6-21-46 w/12,500 Gals. 15%
acid. Gauged 33,607 MCF
after acid on 20-min. blow
down. 72 hr shut in

Ran 8 jts. or 259' of 5 1/2"
liner. Blow down before
& after running liner
gauged 4,814 MCF