


27-34-38W

KANSAS DRILLERS LOG

S. 27 T. 34S R. 38 E
Loc. 1250' FNL & 100' FWL

County Stevens

640 Acres
N

Locate well correctly

Elev.: Gr. 3217'

DF KB

API No. 15 — 189 — 20,289
County Number

Operator

Anadarko Production Company

Address

P. O. Box 351, Liberal, Kansas 67901

Well No.

1

Lease Name

Brown "H"

Footage Location

1250 feet from (N) (S) line 100 feet from (E) (W) line

Principal Contractor

Gabbert-Jones, Inc.

Geologist

Spud Date

10-25-75

Total Depth

3060

P.B.T.D.

Date Completed

11-21-75

Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	646'	Common	550	3% CC
Production	7-7/8"	4-1/2"	10.5#	3060'	Lite Wate Pozmix	500 150	4% gel+12 1/2# Gilsnte .5% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3 SPF		2981-3038' OA
Size	Setting depth	Packer set at			
2-1/16"	3025'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/2000 gallons 15% + 140 ball sealers. Fraced w/60,000 gallons water + 60,000# Riversand.	2981-3038' OA

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
SI for Pipeline Connection	Flowing
RATE OF PRODUCTION PER 24 HOURS	Oil Gas Water Gas-oil ratio
	bbls. CWHOF 1722 MCF bbls. CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval(s)
Will be sold	2981-3038' OA Council Grove A

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Anadarko Production Company

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

1

Lease Name

Brown "H"

Gas

S 27 T 34S R 38 E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

Clay-Sand

0

360

Clay-Sand

360

590

Redbed

590

1010

Redbed-Anhy-Sand

1010

1446

Sand-Redbed-Anhy

1446

1786

Anhy-Shale

1786

2258

Shale-Lime

2258

2346

Lime-Shale

2346

3060

Total Depth

3060

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Stanley Shoemaker

Signature

Division Office Supervisor

Title

December 8, 1975

Date