

29-34-38W


KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCHAPI No. 15 — 189 — 20,275
County Number

S. 29 T. 34 S. R. 38 W

Loc. 1390' FSL & 500' FEL

County Stevens

640 Acres
N

Locate well correctly

Elev.: Gr. 3265.2'

DF KB

Operator

Anadarko Production Company

Address

Box 351, Liberal, Kansas 67901

Well No.

1-A

Lease Name

Morris "A"

Footage Location

1390 feet from (N) (S) line 500 feet from (E) (W) line

Principal Contractor

Gabbert-Jones, Inc.

Geologist

Spud Date

6-10-75

Total Depth

3090'

P.B.T.D.

Date Completed

7-24-75

Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	573'	Common	500	3% CC
Production	7-7/8"	4-1/2"	10.5#	3089'	Lite Wate Pozmix	500 150	4% gel 12 1/2 Gilsonite .5% CFR-2

AUG 15 1975

WINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3 SPF		3003'-3062' OA
Size	Setting depth	Packer set at			
2-3/8"	3035'				

TUBING RECORD

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/2000 gallons 15% + 105 ball sealers. Fraced w/60,000 gallons water + 60,000# Riversand	3003'-3062' OA

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)		
SI for Pipeline connection		Pumping		
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	CAOF 4172 MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)	
Will be sold			3003'-3062' OA	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

