

90105

32286

A-4-85

MAP NO. K-83 ELEV. 3238 DF  
 STATE Kansas COUNTY Stevens SEC. 15 Twp 34S Rge 38W  
 OPERATOR Anadarko Prod. Co. LOC. App C SW/4  
 WELL NO. 1A-15 FARM NAME Kelly "B" 1320 FT. FROM S LINE  
 POOL Wildcat 1460 FT. FROM W LINE  
 FR. 10-12-60 SPUD. 9-28-60 COMP. 3-28-61 of Sec.

CONT./GEOL. Schaefer Drlg. Tools

COMPLETION RECORD  
 NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD

a. P.G. 3044-56 16 10,000Atc, F10X10

b. \_\_\_\_\_

c. \_\_\_\_\_

d. \_\_\_\_\_

a I. P. OIL/DIST. WTR. COF GAS 409 M.C.F.P.D. CHK. HRS.

b " " " " " "

c " " " " " "

d \_\_\_\_\_

~~Temp. Abandoned~~

D & A ( )

SIP# \_\_\_\_\_ FI TP # \_\_\_\_\_ FI CP# \_\_\_\_\_ SIBHP \_\_\_\_\_

GOR. \_\_\_\_\_ GR. \_\_\_\_\_ PBDT \_\_\_\_\_ TD 6590

SIZE	DEPTH	CASING - CEMENT RECORD		DEPTH	W/SAX.
		W/SAX.	SIZE		
<u>13 3/8"</u>	<u>599</u>	<u>500</u>	<u>4 1/2"</u>	<u>3135</u>	<u>150</u>
<u>8 5/8"</u>	<u>1769</u>	<u>300</u>			

OPERATOR Anadarko Prod Co. WELL NO. #1A-15 Kelly "B" ELEV. 3238 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			<u>Krider</u>	<u>2645</u>	
			<u>Winfield</u>	<u>2734</u>	<u>+504</u>
			<u>Council Grove</u>	<u>2965</u>	<u>+273</u>
			<u>Admire</u>	<u>3214</u>	
			<u>Wabaunsee</u>	<u>3396</u>	
			<u>Toronto</u>	<u>4245</u>	
			<u>Lansing</u>	<u>4351</u>	<u>-113</u>
			<u>Marmaton</u>	<u>5072</u>	
			<u>Cherokee</u>	<u>5348</u>	
			<u>Morrow</u>	<u>5890</u>	<u>2652</u>
			<u>Morrow Sand</u>	<u>6329-68</u>	<u>3091</u>
			<u>Chester</u>	<u>6379</u>	<u>3141</u>
			<u>Ste Genevieve</u>	<u>6542</u>	<u>3304</u>

Spud 9-28-60, 13 3/8" @ 599 w/500 sx, Stk DP @ 1450, Rc. LC @ 1476, Rc. 8 5/8" @ 1769 w/300 sx.

DST #1 (Council Grove) 3035-3100, op 130 mins, GTS 8 mins, Ga 190 MCF/100 mins, Rc 348' GCMW, ISIP 422/20 mins, FP 45-67, SIP 422/20 mins.

DST #2 (Lower Morrow) 6277-6348, op 1 hr, Rc 180' GIP + 2650' GCSW, ISIP 1845/20 mins, FP 653-1333, FSIP 1824/20 mins.

RTD 6590, E-Logs & GR, (lost log tool & rec). 4½" @ 3135/150 sxs.

MICT, CO 3120.

P 8/3110-14, swb-NS, 1500 Ac, swb/SSG + 1½ BXWPH, set BP @ 3100.

P 8/3044-48, 8/3052-56, 10,000 Ac, G 280 MCF, frac 10,000 X  
10,000 Sd, swb all ld, Swb 20 GWPH, g TWIM, 10 hr BD, gas  
TSTM + 20 GWPH. 156 hr BD g 193 MCF + 146 BXW, SICP 375#.  
g 157-110 MCF/NT, SICP 265#, g 124 MCF, FCP 318#.

POP

Pumped XW

Temp. Abandoned.

CG - 409 MCF - SICP 409.2

LIBERAL TOPS

rfc 3044-56

3240 KB

3228 Gr.

Winfield 2734 (+506) 494

Council Grove 2965 (+275) Tst 190 MCF - Perf & trtd - Tst XW w/SSG

Wabaunsee 3396 (-156) 2988

Topeka 3570 (-330)

Heebner 4220 (-980)

Toronto 4244 (-1004)

Lansing 4494 (-1254) 4350

Morrow 5890 (-2650)

53 Sand 6328 (-3088) 25/36, NT TG + 6 CFW

Chester 6368 (-3128)

Sand 6488 (-3248) 1/18, NT

St. Gen 6542 (-3302)

RTD 6590