

State Geological Survey WICHITA, BRANCH


2-34-39W

KANSAS DRILLERS LOG

S. 2 T. 34S R. 39 ^{RC}
W
Loc. 1390' FWL & 2630' FNL

County Stevens

640 Acres
N



Locate well correctly
Elev.: Gr. 3246.5'

DF _____ KB _____

API No. 15 — 189 — 20,291
County Number

Operator

Anadarko Production Company

Address

P. O. Box 351, Liberal, Kansas 67901

Well No.

1

Lease Name

Nix "A"

Footage Location

2630 feet from (N) (SX) line 1390 feet from (E) (W) line

Principal Contractor

Gabbert-Jones, Inc.

Geologist

Spud Date

10-31-75

Total Depth

3023'

P.B.T.D.

Date Completed

11-26-75

Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	431'	Common	450	3% CC
Production	7-7/8"	4-1/2"	10.5#	3015'	Lite Wate Pozmix	500 150	4% gel 12 1/2 # Gilsnte .5% CFR-2

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement
----------	-------------	--------------

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
---------------	-------------	----------------

TUBING RECORD

Size	Setting depth	Packer set at
2-1/16"	2959'	

2 SPF

2982-92'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/500 gallons 15% + 25 ball sealers.	2982-92'

INITIAL PRODUCTION

Date of first production SI for Pipeline Connection	Producing method (flowing, pumping, gas lift, etc.) Flowing
RATE OF PRODUCTION PER 24 HOURS	Oil bbls. CWHOF 2648
	Gas MCF
	Water bbls. CFPB
Gas-oil ratio	
Disposition of gas (vented, used on lease or sold) Will be sold	Producing interval(s) 2982-92 Council Grove

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Anadarko Production Company

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

1

Lease Name

Nix "A"

Gas

S 2 T 34 S R 39 K
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

**SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.**

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME _____

DEPTH

Clay-Sand

0

400

Redbed

400

1513

Shale-Anhy

1513

1875

Shale-Shale w/Lime Stks

1875

2257

Lime-Shale

2257

3023

Total Depth

3023

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Stanley Shoemaker

Signature

Division Office Supervisor

Title

December 8, 1975

Date _____