

**KANSAS DRILLERS LOG**

State Geological Survey  
WICHITA, BRANCH


13-34-39W

S. 13 T. 34S R. 39 W

Loc. 1250' FS & EL

County Stevens

640 Acres  
N



Locate well correctly

Elev.: Gr. 3283.8'

DF \_\_\_\_\_ KB \_\_\_\_\_

API No. 15<sup>189</sup> Stevens — 20-296  
County Number

Operator  
Anadarko Production Company

Address  
Box 351, Liberal, Kansas 67901

Well No. 1 Lease Name Mantzke "A"

Footage Location  
1250 feet from (N) (S) line 1250 feet from (E) (W) line

Principal Contractor Geologist  
Gabbert-Jones, Inc.

Spud Date Total Depth P.B.T.D.  
1/1/76 3055

Date Completed Oil Purchaser  
1/26/76

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
	12 1/4	8-5/8	20	527	Common	550	3% CC
	7-7/8	5 1/2	14	3054	Lite Wate Pozmix	500 150	12 1/2% Gil+4% Gel 5% CFR-2

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3 SPF		2977-3035

**TUBING RECORD**

Size	Setting depth	Packer set at
2-1/16	2988	

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
Acidized w/2000 gals 15% HCL + 125 Ball Sealers. Frac	2977-3035 O.A.
w/60,000 gals wtr + 60,000# Riversand.	

**INITIAL PRODUCTION**

Date of first production SI for Pipeline Conn.	Producing method (flowing, pumping, gas lift, etc.) Flowing
RATE OF PRODUCTION PER 24 HOURS	Oil bbls. Gas MCF Water bbls. Gas-oil ratio CFPB
	CW HOF 2670 MCF
Disposition of gas (vented, used on lease or sold) Will be sold.	Producing interval(s) 2977-3035 O.A.

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator  
Anadarko Production Company

DESIGNATE TYPE OF COMP.: OIL, GAS,  
DRY HOLE, SWDW, ETC.:

Well No. 1 Lease Name Mantzke "A" Gas

S13 T 34S R39 X  
W

**WELL LOG**

SHOW GEOLOGICAL MARKERS, LOGS RUN,  
OR OTHER DESCRIPTIVE INFORMATION.

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Clay and Sand	-0-	415		
Clay	415	480		
Redbed	480	1260		
Sand-Shale-Anhydrite	1260	1791		
Anhydrite- Shale	1791	1825		
Shale	1825	1966		
Shale-Anhydrite	1966	2313		
Lime and Shale	2313	3055		
Total Depth	3055			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received \_\_\_\_\_  
Signature: *Stanley R. Shoemaker*  
Stanley R. Shoemaker, Division Office Supervisor  
Title  
March 31, 1976  
Date