

KANSAS DRILLERS LOG


State Geological Survey
WICHITA, BRANCH

14-34-39W

S. 14 T. 34S R. 39 E W

Loc. 1250' FN & EL

County Stevens

640 Acres
N

Locate well correctly

Elev.: Gr. 3281.7'

DF _____ KB _____

API No. 15¹⁸⁹ Stevens — 20-299
County Number

Operator

Anadarko Production Company

Address

Box 351, Liberal, Kansas 67901

Well No.

1

Lease Name

Young "A"

Footage Location

1250 feet from (N) (S) line

1250 feet from (E) (W) line

Principal Contractor

Gabbert-Jones, Inc.

Geologist

Spud Date

3/1/76

Total Depth

3065

P.B.T.D.

Date Completed

3/17/76

Oil Purchaser

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
	12 $\frac{1}{4}$	8-5/8	20	526	Common	550	3% CC
	7-7/8	4 $\frac{1}{2}$	10.5	3064	Lite Water Pozmix	500 150	12 $\frac{1}{2}$ # Gil+4% Gel 5% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2 SPF		2979-3045
TUBING RECORD					
Size	Setting depth	Packer set at			
2-1/16	3016				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized 2000 gal 15% HCL + 90 Ball Sealers. Frac w/	2979-3045 O.A.
60,000 gal wtr + 80,000# Riversand.	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
SI for Pipeline Conn.		Flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	CWHOF 1488 MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
To be sold.			2979-3045 O.A.		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Anadarko Production Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Young "A"	Gas
S 14 T 34S R 39 E W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand and Clay	-0-	500		
Redbed	500	997		
Redbed and Sand	997	1660		
Shale and Anhydrite	1660	2063		
Shale and Lime	2063	2355		
Lime and Shale	2355	3065		
Total Depth	3065			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received

Signature

Stanley R. Shoemaker, Division Office Supervisor

Title

March 31, 1976

Date