

16-34-39W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WALTER F. KUHN
Farm- Armstrong "B" No. 1

SEC. 16 T. 34 R. 39W
C SE

Total Depth. 2875'
Comm. 8-22-62 Comp. 8-30-62
Shot or Treated,
Contractor. Earl F. Wakefield
Issued. 2-16-63

County Morton
KANSAS



CASING:
10 3/4" 629' cem w/750 sx.
7" 2840'

Elevation. 3249' RB

Production. 40,940,000 CFG

Figures indicate Bottom of Formations.

surface clay & sand	375
sand	580
red bed & shells	635
red bed	690
red bed & sand	1045
red bed w/shells	1185
gyp	1250
shale w/shells	1315
sand	1465
red bed & shale strain of anhydrite	1650
red bed & shale streaks of anhydrite	1850
shale & shells	1920
anhydrite, sand & shale	2005
shale & shells	2280
shale & lime	2370
lime	2490
lime & shale	2560
lime	2596
lime w/shale	2725
lime & shale	2875
Total Depth	

TOPS: LOG	
Herington	2575
Krider	2600
Winfield	2609
Upper Fort Riley	2730
Lower Fort Riley	2790