

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY

412 Union National Bk. Bldg., Wichita, Kansas

24-34-39W

Company - HARRINGTON & MARSH
Farm - Smith "A" No. 1

SEC. 24 T. 34 R. 39W

Total Depth. 2853'

Comm. 7-27-46

Comp. 8-18-46

Shot or Treated.


Contractor.

Issued. 5-31-47

SW 1/4 SE

140' N of SL 140' E of
WL of SE 1/4

County. Stevens KANSAS



Elevation. 3296 ft

Production. 17,297,000 Gas.

Figures Indicate Bottom of Formations. R.P. 369.5#

CASING:
10 3/4" 800' cem. w/300 sx.
7" 2684' cem. w/800 sx.

surface & gyp	50
clay sand	545
red bed	675
red bed & gyp shells	765
sand	780
gyp	805
red bed	830
red bed & shells	1075
red bed & gyp	1255
red bed gyp & red rock	1510
red bed & gyp	1660
red bed & gyp	1740
red bed, gyp & lime shells	1815
lime & gyp shells	1890
red bed & gyp shells	2035
red bed gyp & lime shells	2155
red bed & shells	2250
lime & shale	2335
lime & shale	2420
anhydrite & shale	2465
lime	2515
lime & anhydrite	2625
lime	2686

CABLE TOOLS:

lime	2733
shale red	2739
lime brkn	2742
lime	2788
lime brkn & shale	2792
red bed	2800
lime brkn	2853
Total Depth	

GAS SHOWS:

1st. gas	100 MCF	
630 MCF		2705
924 MCF		2709
1,008 MCF		2724
1,218 MCF		2730
1,596 MCF		2752
1,848 MCF		2781
1,932 MCF		2781 1/2
2,058 MCF		2840
2,000 MCF		2853

Tops:

Wellington	2290
Hollenberg	2580
Herrington	2640
Krider	2670
Winfield	2745
Ft. Riley	2808