

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY

412 Union National Bk. Bldg., Wichita, Kansas

27-34-39W

Company - HARRINGTON & MARSH
 Farm - Cunningham No. 2


SEC. 27 T. 34 R. 39W

NEc NW

140' SNL, 140' EWL NW $\frac{1}{4}$

County. Stevens

KANSAS



Total Depth. 2783'

Comm. 7-19-46

Comp. 8-6-46

Shot or Treated. Acid. w/17,000 gals.

Contractor.

Issued. 6-7-47

Rotary Tools: 0 -2630'

Cable Tools: 2687-2783'

CASING:

10 $\frac{3}{4}$ " 600' Cem. w/200 sx
 7" 2620' Cem. w/800 sx

Elevation. 3293.24

Production. 30,400,000 Gas

R. P. 364.4#

Figures Indicate Bottom of Formations.

sand, gyp & clay	580
red bed	600
red bed & gyp	830
red bed, gyp & red rock	890
red bed & shells	1230
red bed, gyp shells	1600
red bed & gyp	1755
red bed & shells	1875
lime & shale	1980
lime brkn & shale	2050
shale & shells	2195
red bed & gyp	2270
anhydrite	2345
anhydrite & shale	2435
anhydrite	2585
anhydrite & lime RTD	2630
limo	2687
red bed	2699
lime brkn	2715
lime	2746
red bed	2764
limo	2783

Total Depth

Tops:

Wellington	2310-
Hollenberg	2530-2560
Harrington	2590-2610
Krider	2623-
Winfield	2699-2745
Ft. Riley	2763-2783

Shows:

1st gas	2640
798 MCF	2658
1218 MCF	2665
6,552 "	2673
7,602 "	2678
8,484 "	2682
8,552 "	2700
8,820 "	2712
8,820 "	2783