

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Plotted
27-34-39W

Location Con SE

Sec. 27 T. 34 R. 39W.

Casing Record.


20" 10"
15 1/2" 8 1/4"
15 1/2" 65/8" 2591
15 1/2" 588 53/16"
Total Depth. 2735

Farm. Meyers 'B'
Company. Benedum Trees Oil Co.
Contr.
Comm. 2-17-31

County Stevens, JUL 11 1931

Comp. 3-17-31

Shot Quarts Between.



Correspondence Regarding This Well Should Be Referred To.

Elevation.

Figures Indicate Bottom of Formations.

Initial Production.

Date Issued. 7-11-31

13,650,000G.

Formation	Depth
sand and clay	259
gyp and sand	560
red rock	588
lime	737
gyp and red rock	1140
gyp and shale and lime	1196
lime	1265
shale hard	1300
gyp and lime	1340
red rock	1400
red sand rock	1415
red rock	1430
red rock and sand	1520
red rock and lime shells	1600
red rock and sand	1635
red rock and lime shells	1680
red rock	1770
gyp and lime shells	1850
lime shells and red rock	1995
red rock	2035
sand	2045
red rock	2170
lime	2235
red rock	2317
lime	2377
lime and shale blue	2505
lime	2725
1st gas 2650	
red rock	2735 TD.