

36-34-39W


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - HARRINGTON & MARSH
Farm - Rickard No. 1

SEC. 36 T. 34 S. 39W
SEc NW
50' NS1, 50' WE1 NW $\frac{1}{4}$

Total Depth. 2767'
Comm. 7-30-45 Comp. 9-18-45
Shot or Treated.
Contractor. Midwestern Drlg. Co.
Issued. 6-7-47

County. Stevens
KANSAS



Rotary Tools: 0 -2667'
Cable Tools: 2667-2767'

CASING:

10 $\frac{3}{4}$ " 610' Cem. w/200 sx
7" 2640' Cem. w/900 sx

Elevation. 3282 rh

Figures Indicate Bottom of Formations.

Production. 27,853,000 Gas
Rock Pressure: 381.9#

sand & clay	100
sand, clay & red bed	620
red bed & sand	1168
GYP	1205
red bed & sand	1745
GYP	1775
red bed	1880
red bed & shale	2365
lime & shale	2385
lime & shells	2400
shale & anhydrite	2505
shale, anhydrite & lime	2662
lime RTD	2667
lime	2703
shale blue	2706
shale red	2718
lime	2767
Total Depth	

Tops:
Wellington 2280
Hollenberg 2570-90
Herrington 2620-35
Krider 2650
Winfield 2720-60

Show Gas	2688
Increase	2695
Increase	2703
Increase	2724
Increase (3,800,000 G)	2730