


Company. E. H. ADAIR, A. F. BRANN, et al
 Farm-Netahla No. 1

SEC. 5 T. 34 R. 4W
 SW NW NW

5-34-4W

County Sumner

KANSAS



Total Depth. 4733

Comm 4-1-57

Comp. 4-24-57

Shot or Treated.

Contractor. E. H. Adair Oil Co.

Issued. 7-13-57

Elevation. 1243 KB

Production. Dry

8 5/8 @ 203' w/ 150 sx cmt.
 5 1/2 @ 4733' w/ 75 sx cmt.

Figures indicate Bottom of Formations.

shale & shells	203
red bed & shale	375
shale & shells	1050
shale & lime	1350
anhydrite & lime	1405
lime & shale	1657
lime	1825
lime & shale	2615
lime	2675
lime & shale	3149
sand	3175
shale	3261
lime	3272
shaley sand	3296
sgale	3346
sand	3440
shale	3613
lime	3852
shale	3900
lime	3907
shale	3946
shaley lime	4138
shale	4198
lime	4206
shale	4306
chert	4320
cherty lime & cherty dolomite	4625
shale	4641
lime	4647
shale	4720
black shale	4730
green sandy shale	4731
sand, slight show oil	4733
Total Depth	

TOPS:	ELEC. LOG	SAMPLE
Lansing		3261
Stalnaker sand		3272
Kansas City	3610	3613
Base KC	3853	3852
Mississippi chert	4311	4306
Mississippi lime	4318	4320
Base Mississippi	4622	4625
Kinderhook shale	4645	4647
Chattanooga shale	4719	4720
Simpson shale		4730
Simpson sand		4731