


KANSAS CORPORATION COMMISSION

WELL RECORD

(Mail to Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209)

6-34-4W



API # 15-191-20,307

Lease Name: Misak Well No. 1
 Well Located: Sumner County, Kansas
C NE NW SEC 6 TWP 34S RGE 4W
 Operator: Mack Oil Company
 Address: 812 Union Center, Wichita, Kansas 67202
 Elevation: Ground 1239' D.F. 1344' K.B. 1346' 1246
 Type Well: (Oil, gas, dry hole) dry hole

Drilling Commenced: 10-28 1971 Drilling Completed: 11-8-71 1971
 Well Completed: 19 Total Depth 4790'
 Initial Production: dry

Casing Record

Size: 8 5/8" Set at 226' Size: _____ Set at _____
 Size: _____ Set at _____ Size: _____ Set at _____

Liner Record

Size: _____ Set from _____ To _____

Cementing

<u>Casing Size</u>	<u>Sacks</u>	<u>Type Cement and Additives</u>
<u>8 5/8"</u>	<u>200 sx.</u>	<u>regular cement, 2% gel, 3% HA-5, & 1/4# per sx. flocele</u>
_____	_____	_____
_____	_____	_____

Perforations

<u>Formation</u>	<u>Perforated Interval and Number Shots</u>
<u>Simpson zone</u>	<u>4724-4734</u>
_____	_____
_____	_____
_____	_____

Electric Log Run (Show type log and depths covered)

Laterolog-Gamma Ray-Neutron 226' - 4789'

(Fill in formation and related information on reverse side)

FORMATION, TESTING AND COMPLETION RECORD

6-34-4w

Show Drill Stem Tests,
Well Stimulation and
Production Tests

Formation	Top	Bottom
Shale & Rdbed	0	60
Rdbed & Shale	60	230
Lime & Shale	230	2620
Shale & Lime	2620	2851
Lime	2851	2931
Lime & Shale	2931	3600
Lime	3600	4155
Lime & Shale	4155	4268
Lime	4268	4381
Chat	4381	4423
Lime	4423	4637
Shale	4637	4702
Lime	4702	4752
Sand	4752	4790

no tests



Treat perfs w/100 gals 7½% acid.
Frac perfs w/10,000 gals G.S.W. & 5000#
20-40 sand

1003-101-30301