

17-34-4W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **SUNRAY MID-CONTINENT OIL CO.**
Farm- **Will Shellhamer No. 1**

SEC. 17 T. 34 R. 4W
C SE NE

at Depth. **4864'**
m. **3-14-62** Comp. **4-1-62**
er Treated.
ractor. **Stickle Drlg. Co.**
ed. **7-28-62**

County **Sumner**
KANSAS



CASING:
8" 304' cem w/175 sx.

Elevation. **1244' DF**

Production. **Dry**

Figures Indicate Bottom of Formations.

shale	265
shale & shells	305
shale	400
shale & lime	1115
lime & shale	1290
shale & lime	1490
lime & shale	1575
shale & lime	1659
shale	2968
lime & shale	3440
sand	3519
lime & shale	3738
lime	4053
lime & shale	4317
lime & chert	4427
lime	4736
shale	4828
lime	4852
hard sand	4859
sand	4864
Total Depth	

TOPS: LOG	
Stalnaker	3399
Kansas City	3717
Marmaton	4035
Cherokee	4200
Mississippi	4402
Kinderhook	4752
Simpson	4830

TOPS: SAMPLE	
Base Kansas City	3955