

State Geological Survey

WICHITA BRANCH

KANSAS DRILLERS LOG

15-129-20325
1-34-40W

API No. 15 — 129 — 20,325
County Number

Operator

ANADARKO PRODUCTION COMPANY

Address

P. O. BOX 351, LIBERAL, KANSAS 67901

Well No.

1

Lease Name

CRAWLEY "A"

Footage Location

1250

feet from (N) (X) line

1250

feet from (E) (X) line

Principal Contractor

Gabbert-Jones, Inc.

Geologist

Spud Date

11:30AM 9/9/77

Total Depth

2965'

P.B.T.D.

Date Completed

10/13/77

Oil Purchaser


S. 1 T. 34S R. 40 NE W

Loc. 1250' FN&EL

County MORTON

640 Acres

N



Locate well correctly

3293'

Elev.: Gr.

DF

KB

CASING RECORD

Report of oil strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	640'	Common	550	3% cc
Production	7-7/8"	4-1/2"	9.5, 10.5	2965'	Lite Wate SS Poz	500 150	4% gel .5% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		2910-2952'
			2		2803-2898'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/1500 gals 15% HCL + 50BS	2910-2952'
A/4000 gals 15% + 150 BS; F/200,000 gals wtr + 300,000 # river-sand	2803-2952'

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
SI FOR PL CONNECTION	Flowing
RATE OF PRODUCTION PER 24 HOURS	Oil bbls. 1000 MCF Gas 3BPH bbls. CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval(s) 2803-2952'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
GAS

ANADARKO PRODUCTION COMPANY

Well No.

Lease Name

1

CRAWLEY "A"

S 1 T34S R 40 E4 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Clay-Sand-Redbed	0'	450'		
Sand-Redbed	450'	641'		
Redbed-Anhy-Sand	641'	1295'		
Redbed-Sand-Anhy	1295'	1807'		
Sand-Redbed	1807'	1810'		
Sand-Shale	1810'	2085'		
Shale-Lime	2085'	2283'		
Lime-Shale	2283'	2965'		
TOTAL DEPTH		2965'		
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received

Signature

Paul Campbell, Division Production Manager

Title

October 31, 1977

Date