

2-34-40 W

WELL COMPLETION REPORT AND DRILLER'S LOG

S. 2 T. 34S R. 40 ^{EX}W
Loc. 1250 FNL & 2310 FEL
County Morton
640 Acres
N

API No. 15 — 129 — 20,394
County Number

Operator
Anadarko Production Company

Address
P. O. Box 351, Liberal, Kansas 67901


Well No. 1 Lease Name FATZER "A"

Footage Location
1250 feet from (N) line 2310 feet from (E) line

Principal Contractor Gabbert-Jones, Inc. Geologist

Spud Date 6/12/79 Date Completed 6/16/79 Total Depth 2985' P.B.T.D. 2910'

Directional Deviation 1/2 deg @ 2263' Oil and/or Gas Purchaser



Locate well correctly
Elev.: Gr. 3303
DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	647	Common	500	3% CaCl
Production	7-7/8"	5-1/2"	14# 15#	2984	Litewate Salt Sat. Poz	500 150	Salt Sat. .05% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		2936-39
TUBING RECORD			2		2924-26
Size	Setting depth	Packer set at	2		2805-2892 O.A.
2-3/8"	2985'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/500 gal 15% + 12 BS	2924-2939 O.A.
A/4000 gal 15% HCl + 100 BS	2805-2892 O.A.
F/200,000 gal wtr + 300,000# riversand	2805-2892 O.A.

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
SI for Pipeline Connection		Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	1,700	MCFF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
To be Sold			2805-2892 O.A.		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Anadarko Production Company

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No. 1 Lease Name FATZER "A" Gas

S 2 T 34S R 40^{EX} W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Clay-Sand Redbed	0'	650'	Logs: Rosel GRCL	
Redbed-Anhy-Sand	650'	1350'		
Redbed-Anhy	1350'	1686'		
Redbed-Anhy-Shale	1686'	2028'		
Shale-Lime	2028'	2263'		
Lime-Shale	2263'	2985'		
TD		2985'		

USE ADDITIONAL SHEETS, IF NECESSARY TO COMPLETE WELL RECORD.

Date Received

Paul Campbell
Signature

Paul Campbell, Division Production Manager
Title

July 19, 1979
Date

Date

5-20-0001