

P

3-34-40W

TEXACO, INC. #709410005

STOUT GAS UNIT #2
KEARNY COUNTY, KANSAS

3-34-40W

OPERATION COMMENCED: 3/4/80

OPERATION COMPLETED: 3/11/80

DRILLERS LOG

3/4	0 - 257	Sand and Gyp.
3/5	257 - 632	Sand and Gyp.
3/7	632 - 1865	Sand, Gyp., Shale, Lime
3/8	1865 - 2400	Shale, Lime
3/9	2400 - 2715	Shale, Lime
3/10	2715 - 2990	Shale, Lime
3/11	2990 - 3000	Shale, Lime

CASING RECORD

3/5	Ran 15 Jts. 8 5/8" 24# casing. Set @ 631'. Cement w/250 sks. 35/65 Poz. and 150 sks. Class H, 3% c.c.
3/11	Ran 70 Jts. 5 1/2" 14# casing. Set @ 3000'. Cement w/550 sks. 35/65 Poz, 10% salt