

11-34-40W

KANSAS DRILLERS LOG

S. 11 T. 34S R. 40W E-
XXX

API No. 15 — 129 — 20,356
County Number

Loc. 1250' FN&EL

County Morton

Operator
ANADARKO PRODUCTION COMPANY

Address
P. O. BOX 351, LIBERAL, KANSAS 67901


Well No. 1 Lease Name FOUTS "A"

Footage Location
1250 feet from (N) (X) line 1250 feet from (E) (X) line

Principal Contractor Gabbert-Jones, Inc. Geologist

Spud Date 4/5/78 Total Depth 2965' P.B.T.D. 2954'

Date Completed 4/25/78 Oil Purchaser



Elev.: Gr. 3320.1

DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

| Purpose of string | Size hole drilled | Size casing set (in O.D.) | Weight lbs/ft. | Setting depth | Type cement | Socks | Type and percent additives |
|-------------------|-------------------|---------------------------|----------------|---------------|---------------------|------------|----------------------------|
| Surface | 12-1/4" | 8-5/8" | 20# | 647' | Lite Wate SS Poz | 500 150 | 4% gel 2% tic |
| Production | 7-7/8" | 4-1/2" | 10.5# | 2965' | Lite Wate SS Poz | 500 150 | 4% gel .2% Tic |
| | | | | | | | |
| | | | | | | | |

LINER RECORD

PERFORATION RECORD

| Top, ft. | Bottom, ft. | Sacks cement | Shots per ft. | Size & type | Depth interval |
|----------|-------------|--------------|---------------|-------------|----------------|
| | | | 2 | | 2915-2950' |
| | | | 2 | | 2801-2901' |

TUBING RECORD

| Size | Setting depth | Packer set at |
|---------|---------------|---------------|
| 2-1/16" | 2939' | |

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

| Amount and kind of material used | Depth interval treated |
|--|------------------------|
| A/1300 gals 15% + 45 BS | 2915-2950' |
| A/3800 gals 15% + 130 BS; F/160,000 gals wtr + 240,000# river sand | 2801-2901' |

INITIAL PRODUCTION

| | |
|--|--|
| Date of first production SI for PL | Producing method (flowing, pumping, gas lift, etc.) Flowing |
| RATE OF PRODUCTION PER 24 HOURS | Oil bbls. 2185 MCF Water 8 BPH bbls. Gas-oil ratio CFPB |
| Disposition of gas (vented, used on lease or sold) Will Be Sold | Producing interval(s) 2801-2950 OA (Council Grove) |

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator ANADARKO PRODUCTION COMPANY DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: GAS

Well No. 1 Lease Name FOUTS "A"

S 11 T34S R 40 ^E/_{XX}

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

| FORMATION DESCRIPTION, CONTENTS, ETC. | TOP | BOTTOM | NAME | DEPTH |
|---------------------------------------|-------|--------|------|-------|
| Surface Clay | 0' | 134' | | |
| Surface Clay-Sand-Redbed | 134' | 650' | | |
| Redbed | 650' | 717' | | |
| Redbed-Anhy-Sand | 717' | 1303' | | |
| Sand-Redbed-Anhy | 1303' | 1687' | | |
| Shale-Lime | 1687' | 2150' | | |
| Lime-Shale | 2150' | 2965' | | |
| TOTAL DEPTH | | 2965' | | |

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____

Paul Campbell
Signature
Paul Campbell, Division Production Manager
Title
June 13, 1978
Date