

KANSAS

15-129-20408
12-34-40W

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 — 129 — 20,408
County Number

Operator
Anadarko Production Company

Address
P. O. Box 351, Liberal, Kansas 67901

Well No. 2 Lease Name CARPENTER "A"

Footage Location
2590 feet from (N) MSX line 1250 feet from (E) MSX line

Principal Contractor Geologist
Gabbert-Jones, Inc. None required

Spud Date Date Completed Total Depth P.B.T.D.
10/13/79 11/19/79 3000 2980


Directional Deviation 3/4 deg @ 3000' Oil and Gas Purchaser CRS-Anadarko

S. 12 T. 34S R. 40 E W

Loc. 2590' FNL & 1250' FEL

County Morton

640 Acres N



Locate well correctly

3312'

Elev.: Gr.

DF 3316' KB 3317'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20	641	Common	500	3% CaCl
Production	7-7/8"	4-1/2"	10.5#	2999	Lite-wate Pozmix	500 150	4% gel salt sat

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	3-1/8 csg gun	2830-2950'

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8"	2958'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/3400 gal 15% HCl	2830-2950'
F/150,000 gal wtr + 225,000# riversand	2830-2950'

INITIAL PRODUCTION

Date of first production SI for pipeline conn	Producing method (flowing, pumping, gas lift, etc.) Flowing
RATE OF PRODUCTION PER 24 HOURS	Oil Gas Water Gas-oil ratio
	bbis. 450 MCF bbis. CFPB
Disposition of gas (vented, used on lease or sold) To be sold	Producing interval (s) 2830-2950'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Anadarko Production Company

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

2

Lease Name

CARPENTER "A"

GAS

S 12 T 34S R 40 ~~E~~ W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand, Redbed	0'	565'	LOGS: Rosel Nuclear Log	
Sand, Shale	565'	650'		
Redbed, Shale	650'	1409'		
Sand, Shale	1409'	1520'		
Shale, Sand	1520'	1911'		
Sand, Shale	1911'	1922'		
Shale	1922'	2396'		
Shale, Lime	2396'	3000'		
TD		3000'		

USE ADDITIONAL SHEETS, IF NECESSARY TO COMPLETE WELL RECORD.

Date Received

Paul Campbell
Signature

Paul Campbell, Division Production Company

Title

November 28, 1979

Date

3-31-80