

34-34-40W

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY PANHANDLE EASTERN PIPE LINE CO.

FARM Mangles


NO. 1

SEC. 34 T. 34 R. 40W

LOC. NE NE SW
3145.0' S of WL &
2440.0' E of WL SW $\frac{1}{4}$

COUNTY Morton

KANSAS



TOTAL DEPTH 2716

COMM. 6-19-50

COMP. 7-30-50

SHOT OR TREATED

CONTRACTOR Moran Brothers, Inc.

ISSUED 12-2-50

CASINO

3/4" OD 476' cem. w/350 sx. circ.
7" OD 2505' cem. w/800 sx.

3378 ind.
ELEVATION 3377.25'

PRODUCTION 5,184,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

sand	40
sand & clay	405
redbed & sand	440
red bed	585
redbed & gyp	700
shale	800
shale & redbeds	1080
shale & gyp	2510
anhyd. & shale	2485
lime R1D	2510
lime	2596
shale	2602
lime	2652
shale	2670
lime	2716
Total Depth	

Tops:

Krider	2532
Winfield	2618
Rt. Riley	2670

Gas Log.

First show	2537	open flow too small to guage
Increase 2553	2656	open flow 656 MCF
"	2590	" " 1,136 MCF
"	2618	" " 1,597 MCF
Blew down to 1,391 MCF at 2622		
Increase	2671	" " 1,728 MCF
" 2671	2673	" " 2,536 MCF
" 2673	2677	" " 3,076 MCF
Blew down to 3000 MCF at 2686		
Increase	2694	" " 3,473 MCF
" 2694	2699	" " 3,667 MCF
Blew down to 3,473 MCF at finish of well.		
Well tested 5,184 MCF on 7-7-50 on 72 hr shut in test		

Hand and R. R. 4164