

90167

4-183W

MAP NO. 82

SEC. 18-34S-40W

STATE Kans. COUNTY Morton

LOC C NW SE

OPER Cities Service Oil Co., Liberal, Kansas

FT/FR LINE

WELL #2 FARM Waymire "A"

FT/FR LINE

Hugoton

ELEV. 3381 GR 3388

DF 3391 KB

CO. Holm Drlg. Tools

GEOL. Vernon Howell

INT. 2750' gas test

F.R. 2/20/64

SPUD

2/22/64

COMP.

4/21/64

TD 2540

FM.

Win

PBTD.

2532

PRODUCING FM.

FROM


TO

PERF W/HOLES

TREATMENT

Chase 2472 - 2528 25 4000A & Frac

I.P. Del Ga; 564,000 Cfgpd (SIP 288#)



Completion Record

Casing Record

8-5/8" @ 390 w/300 sx.

5 1/2" @ 2535 w/700 sx.

Data Inc.

KB Log Tops: *Glorietta 2212151380*

Kri 2438 + 953 LTD 2539 + 852

Win 2514 + 877

RTD 2540, 5 1/2" @ 2535 w/700 sx., CO 2532 PBTD, GRN Log, Pf 11/
2514-28, (Winf) \$ no sho nat, 2000A (15%) Ga 100,000 Cfgpd + 280
GLW/7 hrs, Ga 310,000 Cfgpd + 4 GLW/3 hrs, Pf 7/2472-77, 7/2483-

88. (Kri) Ga 370,000 Cfgpd, dry in 2 hrs, 2000A (15%) Ga 310,000
Cfgpd + 26.7 BW/24 hrs, Wtr decreasing Clor 115,000 PPM, Frac
100,000 gal jell wtr x 100,000# sd, rec part of ld, Gas TSTM,
Ga 4,790,000 Cfgpd + 15 BWPH/88 hrs, 42 hr. Ga 5,540,000 Cfgpd
+ 100 BW/118 hrs, BD Ga 3,230,000 Cfgpd + 100 BWPD, 156 hr. BD
Ga 3,650,000 Cfgpd + 100 BWPD, SIP 240#/48 hrs, Delvi Ga. 564,000
Cfgpd (SIP 288#) Chase 2472-2528, COMPLETE (4/14/64)