


90/68J

12-225W MAP NO. 82 (OWWO) SEC. 22-34S-40W
 STATE Kans COUNTY Morton LOC. C SE NW
 OPER Hamilton Bros FT/FR LINE
 WELL 1 FARM Mingenback (OWWO) FT/FR LINE
 COL Rolla Field-LKc Gas ELEV. GR. 3367 0 DF 3370 0 KB
 CONT. GEOL.
 CO. INT. Note-St Louis new pay horizon
 F.R. 2-14-63 SPUD 6-27-59 COMP. 12-17-63
 TD 6388 FM. St Louis PSTD. Est 6380
 PRODUCING FM. FROM. — TO PERF W/HOLES TREATMENT
 St Louis 6372-6378 12 500A
 I.P. StatePot: P 131 BOPD + 5 BWPD (Gr 49.6 deg)
 Casing Record 7" @2664 4½" @6148



Data Inc.

(KB Spl)	(KB Log) Old
St L 6372 -3002	Top 3440 - 70
DDRTD 6388 -3018	Hb 3788 - 418
	Lans 4070 - 700
OLD INFO: (Same Operator, #1-22	Chero 4950 -1580
Mingenback)	Morr 5490 -2120
DST #1 (Lans) 4235-62, Op 2 hrs,	" sd 5858 -2488
	(Cont)

GTS/3", Ga 287,000 Cfgpd/
 2 hrs, Press NA, ORTD 6148,
 Log, 4½" @6148 w/cem, Pf 40/
 5984-94 (Keyes), 500A, & Frac
 (No size), No comm shows, PB
 4960, Pf 40/4249-59 (Lans), 500A, Ga 1,145,000 Cfgpd, Ga
 1,274,000 Cfgpd/3 hrs from Lans perfs 4249-59, Comp Lans Gas
 Well 10-9-59

B/sd	5872	-2502
Keyes	5973	-2603
Chest	5999	-2629
Miss	6037	-2667
OTD	6148	-2778

→ NEW INFO (3-1-63)

MIR CO & DD 6388 New RTD, Set 2½" csg @6388 w/cem, CO est
 6380, Perf St Louis 8/6372-74, 4/6377-78, NTN, 500A (15%) + 12
 ball sealers, § & Flo 10 BO (new)/13 3/4 hrs-NW (Gr 46.9 deg),
 Set 1½" tbg @6364, Flo (tbg) 133 BO-NW/24 hrs, POP, State Pot:
 Cal P 131 BOPD + 5 BWPD, Gr 46.9 deg, St L Perfs 6372-74 &
 6377-78 - COMPLETED (5-9-63)

OTD 6148 in St Gen
 DD 6388 St. Louis