

2-34-41W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - CITIUS SERVICE OIL CO.
Farm - Commissioners "A" No. 1

SEC. 2 T. 34 R. 41W
NW 1/4 SE
100' S & 100' E of Cen.

Total Depth. 2695 FTD = 2690 Corr. to ground
Comm. 6-10-49 Comp. 6-19-49
Shot or Treated. acid 13,000 gals. 15%
Contractor. Holm-Louis Drlg.
Issued. 2-18-50

County. Horton
KANSAS



Elevation. 3372 Ind.

Production. 8,520,000 gas.
O.F. 20 min.

Figures Indicate Bottom of Formations.

CASING:	
8 5/8" 680 cem. w/300 sx.	
5 1/2" 2535 cem. w/700 sx.	
Sand and shells	110
sand	330
red bed and sand	480
red bed & shells	515
lime	530
shale & sand	585
red bed & chalk	655
red bed	900
lime	955
red bed & sand	1015
lime	1055
red bed & sand	1325
red bed & shale	1405
red bed	1495
anhyd.	1520
shale & shells	1810
red bed & shells	1995
lime	2130
red bed & shale	2245
shale & shells	2300
lime	2465
lime & shale	2685
lime	2695
Total Depth Corr. to ground = 2690	

Perf. 20 shots 2292-96
30 shots 2282-88
20 shots 2270-74

7-2-49 3000 gals. 15% acid 2270-2305
Perf. 110 shots 2224-46.

Acidized 500 gals. 15% acid 2224-46
7-7-49 5500 " " " 2224-46
7-10-49 9000 " 5% acid to all zones.

Tops:	
Herington	2192
Arider	2224
Winfield	2270
Upper Fort Riley	2330
Lower Fort Riley	2400

Perf. 80 shots 2498-2514; no gas 2/3 blr wtr per hr.

Ran Schlumberger electric log.

Set Lane-wells plug at 2340
Perf. 25 shots 2300-2305

6-28-49 500 gals. 15% acid 2300-05
6-30-49 500 gals. 15% acid 2300-05