

4-34-41W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PANHANDLE EASTERN PIPE LINE CO.
Farm- Kneller No. 1

SEC. 4 T. 34 R. 41W
C SE $\frac{1}{4}$
1320' N SL 1320' W SL SE

Total Depth. 2275'
Comm. 6-4-57 Comp. 6-19-57
Shot or Treated.
Contractor. Fees Drlg. Co.
Issued. 10-5-57

County Morton
KANSAS



Elevation. 3383'

Production. 3,000,000 CFG

CASING:

7" 633' w/175 sx cem.
4 $\frac{1}{2}$ " 2261' w/100 sx cem.

Figures indicate Bottom of Formations.

Top soil-clay-sand	98
gravel-sand	216
sand	295
red bed (sh)	327
red bed w/lime strks	425
sand w/shale strks	457
red bed-anhydrite	487
Anhydrite	537
red bed w/lime strks	642
red bed-sand	795
red bed	824
sand	853
Anhydrite	984
sand	1201
red bed	1246
lime-sand-red bed	1340
red bed-lime strks	1365
shale	1382
anhydrite	1487
red bed w/lime strks	1635
Anhydrite-red bed	1765
shale-lime	1890
red bed-lime strks	2130
Dolomite-sand	2242
lime-shale	2275
Total Depth	

TOPS:

Krider	2097
Winfield	2172

Perf.

2205-2215; squeezed.
2186-2192; 2175-2178; 2159-2167;
2152-2156; 2134-2147; 2114-2123.

WELL TREATMENT:

A/500 gals 15% acid - 6-24-57
A/1000 gals 15% acid - 6-30-57
A/1000 gals 15% acid - 7-1-57
F/50,000 gals wtr frac w/37,500#
sand - 7-4-57.