

5-34-41w

NORSEMAN DRILLING, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

WELL NAME: WACKER H #1
SECTION 5-34S-41W
MORTON COUNTY, KANSAS

COMMENCED: DECEMBER 6, 1993

COMPLETED: DECEMBER 10, 1993

API #15-129-21218

OPERATOR: ANADARKO PETROLEUM CORPORATION

Depth		Formation	Remarks
From	To		
0	1014	Sand & Redbed	Ran 16 jts of 24#
1015	1159	Glorietta Sand	8 5/8" csg set @
1160	1770	Redbed	660'; w/200 SX of
1771	2325	Lime-Shale	Class H pozmix-2% CC
			1/4# SX Floceal
			Tailed with 150 SX
			Class H-3%CC; 1/4#
			Floceal; 1" w/100 SX
			25/75 pozmix.
			Job complete at
			5:15 a.m.; 2nd 1"
			w/100 sx 25/75
			pozmix. Job
			complete 8:15 a.m.
			12/7/93.

Ran 54 jts. 5 1/2" 15.50#, Set @ 2322'; Cement w/275
SX 25/75 Pozmix; 2% CC; 1/4# Floceal; Tailed w/150 SX
Common; 2% CC; Plug down @ 12:00 a.m. on 12/10/93

STATE OF KANSAS)I, the undersigned, being duly sworn on
oath, state that the above Drillers' Well
Log is true and correct to the best of my
knowledge and belief and according to the
COUNTY OF SEDGWICK)records of this office.

NORSEMAN DRILLING, INC.

James P. Reilly
JAMES P. REILLY, PRESIDENT

RECEIVED
KANSAS CORPORATION COMMISSION

Subscribed & sworn to before me this

December 16, 1993

MAY 24 1994

CONSERVATION DIVISION
WICHITA, KS

My Appointment Expires:

August 25, 1996

Mary F. Combs
Mary F. Combs, Notary Public
8515 S. West Street
Wichita, KS 67233

